



TENDER REQUEST
for
Repairs to Bar River Hall, 14 Lapish Road

Job 1 - Remove the existing three bottom runs of siding on the river side of the hall from the furnace room to the bathroom - will see bulge in the siding.

Remove existing pwf plywood on the foundation in the same area to expose the rim joists and failing floor joist.

Support and change or sister in new joists, approximately 20' and replace rim joists as well as all sheathing that had to be removed to make repairs.

Replace all pwf plywood removed to make the repairs and install 6 mill poly on the grounds in the repaired area.

Job 2 - Replace all existing 8" x 16" foundation vents and framing on the two existing vents on the driveway or parking lot side. Frame and install one new vent in the centre foundation wall in the same parking lot side and two new vents in the kitchen, end of the hall. Vents to be removable from the exterior to install insulation in the fall. Eight vents total.

Job 3 - Under the main section of the hall install 6 mill poly in the entire area.

Please submit tender to Phyllis L. MacKay, Clerk-Treasurer,
Township of Laird, 3 Pumpkin Point Road West, by Wednesday,
August 19, 2020 at 2 p.m.

Questions can be directed to the above noted person by email at lairdtpw@soonet.ca, or by phone at 705-248-2395.